



Underfloor Heating Statement

It is imperative that underfloor heating systems have been previously commissioned and found to be functioning correctly prior to the floor finish being installed. Ensure that the underfloor heating system is switched off 48 hours prior to the floorcovering installation commencing and remains off for at least 48 hours after the installation is complete.

During the period of decommissioning of the underfloor heating system an alternative heating source should be provided if required to ensure that the area of installation is kept at a constant temperature of between 18°C - 27°C, gradually increase the temperature over a number of days by only a few degrees per day until the desired room temperature is reached. The temperature should never exceed the floorcovering industry agreed maximum of 27°C at the underside of the floorcovering (the adhesive line).

Failure to follow these guidelines can result in the floorcovering debonding, joints opening and on some occasions discolouring, all of which can occur within a long or short period of time.

Underfloor heating must not be operated whilst the protective floor cover is still in place, as it will damage the floor. The underfloor heating can only be activated once the protective cover has been removed.